



# Addendum#1

Project Number: 1800816  
DATE:

Addendum Number: 1

Project Name: Coventry High School – Cafeteria & Janitor Closet Abatement

Date: May 20, 2020

This Addendum is an integral part of the Contract Documents and shall be treated as such. Bidders shall acknowledge receipt of this Addendum on the Bid Form. The following changes shall supersede previously issued Contract Documents to the extent modified by this Addendum.

## REQUESTS FOR INFORMATION

- Q1. Who is responsible for air and visual clearances for the asbestos?  
A1. The Town of Coventry has retained BL Companies for the asbestos visuals and clearances.
- Q2. Can we use chemical or grinding for the mastic?  
A2. Use of chemicals must be compatible with the replacement materials. Grinding is allowed if following requirement for keeping materials wet and HEPA equipped grinders or Blastrac.
- Q3. Can I get a copy of the list attendees?  
A3. List attached.
- Q4. There are 3 ventilator units and the tiles run under them. Do these units need to be removed and floor abated or can the unit remain in place?  
A4. School Maintenance will remove and replace the unit ventilators. Contractor is responsible for removing and replacing tile underneath.
- Q5. The Janitor Closet with the floor mounted slop sink, what type of flooring replaces the current one? Is it VCT or some type of quarry tile??  
A5. The floor in the Janitor Closet shall be the same VCT as specified for the cafeteria.
- Q6. What are the hours of operation for the school during the shut down and floor replacement phase?  
A6. Hours are 6am to 6 pm Monday thru Friday but additional hours can be scheduled.
- Q7. Is it possible for our abatement subcontractor to visit the site to get a better understanding of the scope of work required to be done at the area?  
A7. Yes, they can schedule a time by contacting Bill Trudelle at [WTrudelle@coventryct.org](mailto:WTrudelle@coventryct.org)



# Addendum#1

## **Invitation to Bid**

### **Remove**

Coventry Public Schools (CPS) seeks to abate approximately 18,083 square feet of Vinyl Asbestos Tile (VAT) flooring and mastic at Coventry High School, along with associated cove base, adhesive, carpet and glue and replace with Vinyl Composition Tile.

### **Replace with the following:**

Coventry Public Schools (CPS) seeks to abate approximately 3,260 square feet of Vinyl Asbestos Tile (VAT) flooring and mastic at Coventry High School, along with associated cove base and adhesive and replace with Vinyl Composition Tile and cove base.

**END OF ADDENDUM #1**

## WALK THROUGH ATTENDEES

Oscar's Abatement LLC.

[oabatement@aol.com](mailto:oabatement@aol.com)

Air Quality Experts

[MDichard@aqenh.com](mailto:MDichard@aqenh.com)

Lee Setzler

[Lees@johnboyleco.com](mailto:Lees@johnboyleco.com)

Acme Abatement Contractor

[Sopheak@acme-abatement.com](mailto:Sopheak@acme-abatement.com)

ENCO

[richardshultz@sbcglobal.net](mailto:richardshultz@sbcglobal.net)

Bestech

[Estrickland@bestechct.com](mailto:Estrickland@bestechct.com)

Abatement Industries Group

[john@aigcorp.org](mailto:john@aigcorp.org)

Wiese Construction

cell 860-941-9735

Diversity construction

[mdaigle@diversitycg.com](mailto:mdaigle@diversitycg.com)

ACR

[SManii@AnthonyCRose.com](mailto:SManii@AnthonyCRose.com)

F&E Frontier Environmental LLC

[frontierenvironmental@gmail.com](mailto:frontierenvironmental@gmail.com)